

AL-KO THERM refrigeration piping requirements

Please make sure that the following points are taken care of by the time of refrigeration piping:

- The mechanical installation of the ventilation system is complete.
- Lifting platforms, lifting tools and equipment, scaffolding and ladders are provided onsite according to the provisions of the Employers' Liability Insurance Association, safety precautions have been taken.
- Clear transport paths have been established, packaging material disposal is taken care of, area is accessible during normal business hours (unless otherwise agreed upon) and there is sufficient illumination and sufficient current for both power and lighting.
- Any other onsite conditions and requirements have been pointed out in advance and coordinated.
- It has been coordinated in advance whether or not and/or to what extent onsite technical personnel must be made available for support. Their presence must be ensured as per agreement.

Notes:

- The refrigeration piping in/on the housing includes the completion of the refrigeration piping between housings mechanically linked to an RLT equipment unit.
- The individual housings are pre-piped with regards to refrigeration according to onsite specifications, have closed connection points and pressure-tested with nitrogen. Connection materials are already supplied with the equipment.
- Separate from this, the piping between mechanically unlinked RLT equipment units and refrigeration functional elements (e.g. separate supply/exhaust air) are not a part of the refrigeration piping in/on the equipment (additional piping).
- The additional piping between mechanically unconnected RLT equipment units and refrigeration functional elements (e.g. separate supply/exhaust air) is not a part of the refrigeration piping to be completed in advance in/on the housing, and must be completed onsite, incl. any cabling between mechanically unconnected RLT equipment and refrigeration functional elements (e.g. separate supply/exhaust air) still necessary.
- The refrigeration piping does not include a claim for free fault rectification, even during the warranty period.
- The refrigeration piping does not include liability for the proper planning, dimensioning and implementation of the complete system.
- We are not liable for any damage caused by transport.
- If any of the above-listed preliminary work has not been provided or is not available, then a new visit will be necessary. A second visit will only be carried out with an additional charge according to the time and travel expenses incurred. Our current charge rates apply. A new visit will only be carried out with verification of the work to be done.
- Wait times and fault rectifications for which we are not responsible will also be charged according to the effort involved.

Please fill out page 2 and return to the e-mail address listed above!

AL-KO THERM GMBH
Hauptstrasse 248 - 250 • 89343 Jettingen-Scheppach

Telephone no.: +49 8225 39 - 2574
Fax no.: +49 8225 39 - 2626
E-mail: Service.Center@al-ko.com



Please fill out and return to the e-mail address listed above!

AL-KO THERM refrigeration piping

Client confirmation:

We hereby confirm that all necessary requirements (as per page 1) have been met for the desired refrigeration piping.

Desired refrigeration piping date: _____

Date according to agreement, we must be notified of the desired date at least 8 weeks in advance.

AL-KO order no.: _____

Project: _____

Equipment location address: _____

Onsite contact: _____

Company: _____

Mobile no.: _____

Date/Location

Signature/Company stamp