

AL-KO THERM end of housing cabling requirements

Please make sure that the following points are taken care of by the time of end of housing cabling:

- RLT equipment installation is complete.
- Lifting platform, scaffolding and ladders are provided onsite according to the provisions of the Employers' Liability Insurance Association, safety precautions have been taken.
- The switch cabinet, ventilation systems and other systems are fully available and accessible.
- Clear transport paths have been established, packaging material disposal is taken care of, area is accessible during normal business hours (unless otherwise agreed upon) and there is sufficient illumination and sufficient current for both power and lighting.
- Any other onsite conditions and requirements have been pointed out in advance and coordinated.
- It has been coordinated in advance whether or not and/or to what extent onsite installation personnel must be made available for support. Their presence must be ensured as per agreement.

Notes:

- As an option, the individual housings of the ventilation systems are brought back to the factory and pre-wired with rolled up cables according to specifications.
- The end of housing cabling after delivery merely includes wiring, feed throughs and connection services for the scope delivered by AL-KO in/on the RLT equipment (housing, internal switch cabinet, field equipment to be attached). Separate from this, cabling, feed throughs and connection services of third-party equipment (onsite field equipment, switch cabinets) as well as those supplied by AL-KO, but not attached in/on the RLT equipment, along with field equipment or control cabinets positioned outside of the RLT equipment are generally excluded.
- The feed-in of the onsite power supply into the RLT equipment / switch cabinet is excluded in any case according to VDE regulations.
- The end of housing cabling on the construction cannot be combined with the commissioning / must not be confused with regards to personnel!
- The end of housing cabling does not include a claim for free fault rectification, even during the warranty period.
- The end of housing cabling on the ventilation system does not include liability for the proper planning, dimensioning and implementation of the complete system.
- If any of the above-listed preliminary work has not been provided or is not available, then a new visit will be necessary. A second visit will only be carried out with an additional charge according to the time and travel expenses incurred. Our current charge rates apply. A new visit will only be carried out with verification of the work to be done.
- Wait times and fault rectifications for which we are not responsible will also be charged according to the effort involved.

Please fill out page 2 and return to the e-mail address listed above!

AL-KO THERM GMBH
Hauptstrasse 248 - 250 • 89343 Jettingen-Scheppach

Telephone no.: +49 8225 39 - 2574
Fax no.: +49 8225 39 - 2626
E-mail: Service.Center@al-ko.de



Please fill out and return to the e-mail address listed above!

End of housing cabling after delivery by AL-KO THERM

Client confirmation:

We hereby confirm that all necessary requirements (as per page 1) have been met by the time of housing cabling.

Desired cabling date: _____

Date according to agreement, we must be notified of the desired date at least 3 weeks in advance.

AL-KO order no.: _____

Project: _____

Equipment location address: _____

Onsite contact: _____

Company: _____

Mobile no.: _____

Date/Location

Signature/Company stamp